

SCOPE OF WORK

Station : Paradeep

Page 1

Name of work : Provision of 1000 ltrs tank at P-71 Bldg at CGRA Paradiip.

SI No.	Brief description of item of work	A/U	Qty
1	Sypply of Manpower Service for supply and fixing of 25 running Meter 20 mm bore UPVC tubes (Make : Astral Supreme Syntex) with all fitting and fixed complete to walls and ceilings or laid in floors.	Piece	1
2	Sypply of Manpower Service for supply and fixing of 25 running Meter 25 mm bore UPVC tubes (Make : Astral Supreme Syntex) with all fitting and fixed complete to walls and ceilings or laid in floors.	Piece	1
3	Sypply of Manpower Service for supply and fixing of 01 number of 1000 litres capacity tripple layered rotational moulded polyethylene water storage tanks (Makes : Astral / Syntex / Supreme) (cylindrical vertical with closed top) incl GI tank nipple and fixed in position all as specified in SSR Part I. Complete all as specified and directed byAGE BR Paradeep.	Piece	7
4	Sypply of Manpower Service for supply and fixing of 01 numbers of 25 mm bore Ball brass float valves, high pressure, with polythene float and flynut screwed for iron pipe or brass ferrule	Piece	7
5	Sypply of Manpower Service for supply of materials for fixing for with modular flyash bricks , straight or curved on plan exceeding 6m mean radius, built in Cement Mortar 1:6 ratio	Cubic Meter	4
6	Sypply of Manpower Service for supply materials required for construction of 15 mm thick rendering in cement mortar (1:4) using water proofing compound @ 3 % by weight of cement in finish coat on other than fair faces of brick wall suerfaces, finished even and smooth without using extra cement	Square Meter	44
7	Supply only integral water proofing compound for plastering / concrete work	KG	2
8	Sypply of Manpower Service with materials required for preparation and applying three coats of white wash on newly plastered surfaces of wall.	Square Meter	44
9	Sypply of Manpower Service with materials required for fixing of 113 Kilogram of mild steel TMT bars 10 mm dia and over cut to length bent to shape as required incl cranking, bending, spirally for hooping for columns hooking ends and binding	Piece	1
10	Sypply of Manpower Service with materials required for form work of 15 Square Meter to soffits of suspended slabs such as roof slabs, floor slabs, landings and similar work; not exceeding 200mm thick (Horizontal or sloping) rough finished surface of concrete.	Piece	1
11	Sypply of Manpower Servicewith materials required for 0.50 Cubic Meter Slabs supported on walls, beams and columns in floors, roofs, landings, balconies, canopies, deck slabs and in shelves and the like of B0 Type 1:2:4 12.5 mm graded.	Piece	1

Name of Firm:

Signature of Proprietor: